

**TOWNSHIP OF NORTH HURON
CONSTRUCTION OF BLYTH SIGN
CONTRACT NO. 25267**

ADDENDUM NO. 1

Plan takers shall note the following:

1. Prior to the start of construction, the Township will determine where the electrical power supply to the existing electrical panel, mounted on the back of the wall, comes from and ensure it is turned off.
2. The height of the flags to be mounted behind the sign shall be increased to 2-20' high and 1-24' high flag poles. The flag poles are to be as noted on the drawings, a commercial grade aluminum pole, similar to those offered by Flags Unlimited or accepted equivalent.
3. In lieu of reconstructing the existing sign board, Contractors are to building a new sign board the same size and with the same material or as otherwise approved by the Contract Administrator. The materials used for the letter must be corrosion resistant. The Contractor shall provide details of the proposed materials and fabrication methods for the Contract Administrator to review and approve before fabrication.
4. The flood light for the sign is to be located within the flower bed in front of the sign. The new flood light shall be adjustable in terms of its ability to tip and focus on the signboard to minimize the amount of light distributed outside of the sign board.
5. With the back wall for Option 2, the masonry block wall on the inside shall be built with 140mm standard grey blocks with 20M rebar and grout filled cores at maximum 1200mm cts. Other aspects to be included in the price of the Option 2 design including the brick veneer on the outside face of the wall and adjustments to the width of the concrete cap on top.

B. M. ROSS AND ASSOCIATES LIMITED
Engineers and Planners
62 North Street
Goderich, ON N7A 2T4
Phone: (519) 524-2641
www.bmross.net

April 17, 2026

Bidder's Signature

Date

(Bidders shall sign and date all addenda and attach to their submission)